# PROPERTY INSPECTION REPORT





PAUL & SUE MCKENZIE PO Box 18572, Christchurch 8641 PAUL. 021 036 7391 FREEPHONE. 0800 036 739 EMAIL. pandsmckenzie@hotmail.com

# **PROPERTY INSPECTION REPORT**

This non-invasive pre-purchase property inspection report is to be read in conjunction with the terms and conditions included in this report.

Report carried out by Paul McKenzie Reg. Master Builder (7872) Licensed Building Practitioner (104802) Report valid for 30 days from date of inspection.

- Address: 13 Broadbent St Riccarton Christchurch
- Client: Wayne and Carolie Blair Jwayneblair@hotmail.com
- Date of report: 15<sup>th</sup> May 2015

Weather: Raining

# SITE

#### Style of house

Single level brick and timber weather-board clad house; built approx in the 1950-60's.

#### **Orientation of living areas**

Living areas face north.

#### Site exposure, contour and vegetation

Flat sheltered site, minimal landscaping.

#### **Retaining walls**

No retaining walls.

#### Fencing

Timber paling fencing in reasonable condition. Deterioration/rot to the rails on the south elevation fencing.

#### Driveway

Tar-sealed, concrete and shingle driveway in older condition. Slumping to the edges of the tar-seal.

#### Surface water control to overall site

Water appears to fall to front of section, water is also ponding on the tar-sealed area.

### **EXTERIOR OF HOUSE**

#### Foundation type

Concrete foundation in good condition; no visible cracking. Viewed above ground level only.

#### Ventilation to foundation

Concrete vents to foundation giving adequate ventilation to sub-floor.

#### **Cladding of exterior**

100 Series brick cladding; minor cracking to mortar-joints, otherwise in good condition. Deterioration/rot to the timber weather-boards to the extension, also evidence of borer. Narrow gap to the top of the weatherboards on the north/east corner. Cement-board cladding to the entry area may contain asbestos.

#### Chimney

Old metal chimney flue has been removed; hole remains open to the weather on the roof.

#### Fascia and gutter

Timber fascia and barges mostly in good condition; hole to the south elevation barge. Metal spouting in older condition.

#### Downpipes

65mm downpipes in good condition; water falls to storm-water outlets.

#### **Outside taps**

No leakage sighted to outside taps.

#### **Snowties to spouting**

No snowties to spouting.

#### Soffits

Cement-board soffits in well-painted condition.

#### Flashings

Timber boards, Hardies-sheet boards and steel lintels above doors and windows in reasonable/older condition.

#### **Structural alterations**

Two bedroom extension on the east elevation. Garage has been converted into two bedrooms and studys.

#### Earthstake to ground

Earthstake not located.

#### **Roof exterior**

Concrete tile roofing to the original part of the house has slight sagging to the hip-blades due to weight of roof and age of house, otherwise appears to be in good order. One sealed roofing tile on the north hip may need replacing. T-rib iron roofing to the extension in dented condition. Corrugate iron to the garage in good order.

#### Penetration of roof eg. vents

All penetrations well-flashed and secured.

#### Television aerials and other

All aerials well-secured.

#### Exterior heat-pump unit

Exterior unit not secured to the base.

#### Exterior windows type

Mix of timber, steel and aluminium windows in good condition. Minor rust to the steel window.

#### **Exterior doors**

Timber doors in good condition.

#### Paths

Minor cracking to concrete paths.

### SUB-FLOOR

#### Accessibility to under-floor

Access to sub-floor through bathroom.

#### Pile type

Concrete piles appear to be in good original condition.

#### Any structural alterations under floor

None evident.

**Fixings for bearers to piles** No fixings as per the practise at time of build.

#### Vapour barrier to ground No barrier.

no parrier.

#### Plumbing to sub-floor

Polybutelene and PVC piping well-supported.

#### Sewer drain leakage

None sighted.

#### Waste pipe to bathroom/kitchen leakage

Well-supported waste-pipes to kitchen and bathroom.

No visual evidence of leaking to pipes when water in kitchen, bathroom and laundry was flowing.

Unsure where one waste-pipe on the exterior of the extension is from as it does not go to a sewer outlet.

#### Ventilation to under floor

Well-ventilated through vents.

#### Type of timber floor

Timber tongue and groove flooring.

#### Insulation to under floor

Double-sided foil insulation well-installed.

### Ground clearance of timber to sub-floor

300-600mm clearance.

### Insect and pest infestation

Borer evident to the bearers.

#### Rotten timber to sub-floor None sighted.

*P&S Construction Ltd Paul McKenzie Ph: 021 0367391 email: pandsmckenzie@hotmail.com* 13 Broadbent St Riccarton Christchurch:15-5-15

# **ROOF SPACE ABOVE CEILING**

#### Accessibility

Good access through bathroom ceiling.

### Type of construction

Heavy timber framed conventional roof; connections appear secure.

#### **Ceiling construction**

100 x 50mm ceiling joists in good order.

#### Under roof building paper and/or netting

No roofing underlay as per the practice for tile roofing at time of build.

### Insulation

R2.6 Batts insulation neatly installed.

#### Plumbing to roof space

Polythene pipes no longer in use.

#### Wiring to roof

Mostly Thermoplastic-sheathed cable wiring (TPS). Cloth wiring to the mains-cable.

#### Low water pressure tank and overflow to outside. Polyurethane tank not secured in roof-space; no longer in use.

Insect infestation None sighted.

Rotten timber None sighted.

#### **Vents into ceiling space** Mechanical vents from the bathrooms into the ceiling-space.

### **INTERIOR**

# Switch board

Switchboard in good condition; two MCB's added. Cloth wiring to the mains-cable.

#### Alarms Smoke alarms operational.

#### Hot water cylinder.

300 litre cylinder restrained outside.

### ENTRY/HALL

**Door** Timber front door well-aligned.

Floor covering Carpet in good condition.

**Walls and ceiling** Plaster walls; timber boarding to the ceiling; all in good condition; no visible cracking.

Lights and plugs All working.

All working.

# **KITCHEN**

Windows Aluminium single glazed in good working order.

Floor covering Tiles in good order.

#### Walls and ceiling

Plaster walls in good condition; no visible cracking. Hard-board tiles to the ceiling are sagging in places.

#### Tiles/splash-back areas

Tiles behind bench in good order; well-sealed to wall.

Bench-top Formica bench-top in good order.

**Dishwasher** Standard dishwasher in place; not tested.

### Oven type and range-hood

Free-standing range not tested. Canopy range-hood in operational order. Venting through the roof.

**Plumbing** No plumbing leakage sighted; high pressure to cold water, low to hot.

#### Cabinetry

Melamine cabinetry has tape missing to the edges, also some water-damage. Drawers are tight to open; need easing. One cupboard door is broken/missing.

### Lights and plugs

All working.

### DINING

**Doors** Timber door is binding at the top.

Floor covering Carpet in good condition.

### Walls and ceiling

Plaster and timber boarding to the walls in good condition; no visible cracking. Hard-board tiles to the ceiling are sagging in places.

#### Lights and plugs

Two light-switches don't appear to be working; balance operational.

# LOUNGE

**Doors** Timber door well-aligned.

#### Windows

Aluminium single glazed in good working order.

Floor covering Carpet in good condition.

#### Walls and Ceiling

Some dents to the plaster walls; balance in good condition. Partition wall has been removed and a beam placed in the ceiling; all well-built.

#### Lights and plugs

All working.

#### Heating

Heat-pump in operational order.

# **BEDROOM WEST**

**Doors** Timber door well-aligned.

#### Windows

Aluminium single glazed in good working order.

### Floor covering

Carpet in good condition.

Walls and ceiling Plaster in good condition; no visible cracking.

Lights and plugs All working.

Wardrobe Built-in wardrobe; door well-aligned.

# **BEDROOM SOUTH/WEST**

**Doors** Timber door well-aligned.

#### Windows

Aluminium single glazed in good working order.

#### Floor covering

Carpet in good condition.

#### Walls and ceiling

Plaster in good condition; no visible cracking.

#### Lights and plugs All working.

**Wardrobe** Built-in wardrobe; sliding doors well-aligned.

# **BEDROOM SOUTH/EAST**

Doors

Timber door well-aligned.

### Windows

Aluminium single glazed in good working order.

Floor covering

MDF timber flooring in good order.

### Walls and ceiling

Plaster-board, timber boarding and brick walls in good order. MDF timber ceiling in good order.

Lights and plugs All working.

Wardrobe No built-in wardrobe.

# **BEDROOM NORTH/EAST**

**Doors** Timber door well-aligned.

Windows Steel single glazed in good working order.

Floor covering Carpet in good condition.

### Walls and ceiling

MDF timber ceiling in good order. MDF timber and brick walls in good order.

Lights and plugs All working.

Wardrobe No built-in wardrobe.

# **BEDROOM/GARAGE NORTH**

**Doors** Aluminium door well-aligned.

Windows Aluminium single glazed in good working order.

**Floor covering** Carpet in good condition.

Walls and ceiling Minor cracking to the MDF walls. Hard-board or ply-wood ceiling in good order.

Lights and plugs All working.

Wardrobe No built-in wardrobe.

# **BEDROOM/GARAGE SOUTH**

**Doors** Aluminium door well-aligned.

### Windows

Aluminium single glazed in good working order. Beads to the fixed window pane beside the door are loose.

Floor covering Carpet in good condition.

Walls and ceiling

MDF walls in good order. Hard-board or ply-wood ceiling in good order.

Lights and plugs

All working.

Wardrobe No built-in wardrobe.

# **BATHROOM ONE**

#### Doors

Timber door well-aligned.

#### Walls and ceiling

Hard-board and formica in good condition; no visible cracking.

#### Window

Timber single glazed in good working order.

#### **Floor covering**

Tiles in good order. Two tiles are missing.

#### Bath and shower

No bath. Cubicle shower with glass door in good order. Mixer works well. No plumbing leakage sighted.

#### Vanity

Vanity in good working order. Acrylic top with cupboards below; no plumbing leakage sighted.

#### Heating/vent

Wall heater; mechanical vent to ceiling; both in working order. Venting to the ceiling-space.

#### Light

Light working.

#### W.C

Pan and cistern in good working order. No plumbing leakage sighted.

#### Laundry area

Washing machine to bathroom; no tub.

### **BATHROOM TWO**

#### Doors

Timber door well-aligned.

#### Walls and ceiling

Plaster to the ceiling is in poor/water-damaged condition. Tiles to the walls in good order.

#### Window

Timber single glazed in good working order.

### Floor covering

Vinyl in good condition.

#### Bath and shower

Acrylic bath with tile surround in reasonable order. The end of the bath requires re-sealing. Rubber wedge to the bath screen door is loose. Screen doors are not working correctly on the track. Shower over bath in good working order; mixer works well. No plumbing leakage sighted.

#### Vanity

Vanity in good working order. Acrylic top with cupboards below; no plumbing leakage sighted.

#### Heating/vent

Light/fan unit in operational order. Mechanical vent to the ceiling in working order.

#### Lights and plugs

Only one of the five lights is working. One rocker to the switch on the wall is not working correctly/sticking.

#### W.C

Pan and cistern in good working order. No plumbing leakage sighted.

## GARAGE

#### Type of garage

Separate double garage has been converted to bedrooms. Check Council consent for habitable use.

#### Doors

Single glazed doors in good alignment.

#### Walls and roof

Hardies-board and iron exterior cladding in good order. Corrugated iron roof in good order.

#### Windows

Aluminium single glazed in good order. Loose beads to one window.

#### Floor

Unable to view under carpet.

#### Lights and plugs

All working.

#### **Moisture readings**

#### Taken with Surveymaster Protimeter dual-function moisture meter.

It should be emphasized that these readings are non-invasive and serve as a guide only, they cannot determine conditions within the walls.

Normal moisture content range has been understood and acceptable at 12% - 14%.

The NZ standard 3002 since 2005 requires that H1.2 treated framing timbers not be allowed to exceed 20% moisture content.

At time of build, moisture content will not exceed 14% before wall linings are installed.

#### Readings taken beside doors and windows:

North: 9.8% South: 12.2% East: 11.8% West: 9.9%

Bathroom one: Right side of shower: 15.8% Left side of shower: 13.8%

Bathroom two: Right side of shower/bath: 14.0% Left side of shower/bath: 15.8%

#### Services

Mains power, sewer and water.

#### Levels

East-West: Out of level by 20mm over 9mts: lower to east. North-South: Out of level by 12mm over 12mts: higher to north. 15mm lower to the centre of the house.

#### Summary

House appears to be in a sound condition, as much as can be determined through a visual, non-invasive inspection.

Areas noted throughout report include:

- Minor cracking to the brick mortar-joints.
- Deterioration/rot to the timber weather-boards to the extension, also evidence of borer.
- Narrow gap to the top of the weatherboards on the north/east corner.
- Timber fascia and barges mostly in good condition; hole to the south elevation barge.
- Cement-board cladding to the entry area may contain asbestos.
- Old metal chimney flue has been removed; hole remains open to the weather on the roof.
- Concrete tile roofing to the original part of the house has slight sagging to the hipblades due to weight of roof and age of house; one sealed roofing tile on the north hip may need replacing.
- T-rib iron roofing to the extension in dented condition.
- Exterior heat-pump unit not secured to the base.
- Minor cracking to concrete paths.
- Unsure where one waste-pipe on the exterior of the extension is from as it does not go to a sewer outlet.
- Borer evident to the sub-floor bearers.
- Mostly Thermoplastic-sheathed cable wiring (TPS); cloth wiring to the mains-cable.
- Polyurethane tank not secured in roof-space; no longer in use.
- Hard-board tiles to the kitchen and dining room ceiling are sagging in places.
- Melamine cabinetry has tape missing to the edges, also some water-damage.
- Drawers are tight to open; need easing and one cupboard door is broken/missing.
- Two light-switches in the dining room don't appear to be working; balance operational.
- Some dents to the lounge plaster walls.
- Beads to the fixed window pane beside the door in bedroom south are loose.
- Two tiles are missing to the bathroom floor.
- Plaster to the bathroom-two ceiling is in poor/water-damaged condition.
- The end of the bath requires re-sealing.
- Rubber wedge to the bath screen door is loose; screen doors are not working correctly on the track.
- Only one of the five lights is working in bathroom-two, also one rocker to the switch on the wall is not working correctly/sticking.
- Separate double garage has been converted to bedrooms; check Council consent for habitable use.

#### NB:

Various building materials used pre 1987 eg: sheet Hardies cement-board products, soffit linings, stippled ceilings, insulation etc may contain asbestos. No testing for asbestos is undertaken in this report.

Borer was sighted to the house timbers as noted, however, given the age of the house and that untreated timber was likely to have been used in the construction, borer could be present in other areas.

Should you need clarification of any matter arising from this report you can contact me on 021 0367391.

Regards

Paul McKenzie



West elevation to road.



New extension to east elevation.



Insecure heat-pump.



Hole in roof from previous chimney.



Very minor cracking to mortar-joints.



Borer to weather-boards.



Slumping to tar-sealed driveway.



Deteriorating fence rails.



South/east elevation.



Rear of garage in good order.



South/east hip blade is sagging.



Secure side of garage cladding.



Secure hot water cylinder.



Hole in barge capping may allow south/ west rain inside.



East extension.



Two bedroom extension to east. Steel window beginning to rust.



Extension to east.



Borer to cladding.



Small hole to cladding.



Sub-floor to extension secure.



Tile roofing secure.



Not sure what this waste-pipe is for.



Rotten board and borer to east elevation.



Holes around waste-pipes should be plastered.




Water runs off the end of the lean-too roofing spouting.



South elevation.




Water-tank in roof-space not secured.



Hole in roof from previous chimney flue.



Secure shelter to south elevation.



Mostly TPS wiring to ceiling.



Insulation well-placed; new ceiling beam well-built over lounge area.



Dents in wall of lounge.




Secure roof framing.



Tiles missing to bathroom floor.




Switch board in good order; cloth mains cable.



Sealant required to end of bath.



Bathroom.



Kitchen.



Screen-doors to bath not operating correctly.



Bedroom.




Rubber wedge to bath screen-doors are loose.



Kitchen.



Kitchen ceiling tiles are sagging.



Bedroom.



Kitchen/dining.



Bedroom.



Lounge.



Bathroom.



Bedroom.



Secure insulation to sub-floor.



Secure sub-floor.



Loose door to kitchen units.




Galvanised piping and PVC waste-pipes.



Sub-main to garage.



Garage.



Garage.




Garage/bedroom.



Loose beads to window sash in the south bedroom.



Garage.



Paint deteriorating to bathroom ceiling.

	CERTIFICATE OF INSPECTION IN ACCORDANCE
	WITH NZS 4306:2005
	Client: Wayne & Coralie Blait
	jwayneblait@Lotmail.com
	Site address: 13 Broadlest ST Riccaston chich
	Inspector - Name: Paul McKenzce
	company: P&S constanction Ltd
	Qualifications: Rug Master Builder 7872: LBP
	Date of inspection: 15 105 2015
Г	he following areas of the property have been inspected: Yes No
	(please tick)
	(a) Site
	(b) Subfloor
	(c) Exterior
22	(d) Roof exterior
	(e) Roof space
8	
•	(f) Interior
	(g) Services
	(h) Accessory units, ancillary spaces and buildings govage -
A	ny limitations to the coverage of the inspection are detailed in the written report.
c	Certification:
	hereby certify that I have carried out the inspection of the property site at the above address in accordance ith NZS 4306:2005 <i>Residential property inspection</i> – and I am competent to undertake this inspection.
S	ignature:Date:
F	m46 . ( ]
1 Str. Barr	An inspection carried out in accordance with NZS 4306:2005 is not a statement that a property complies with the requirement of any Act, regulation or bylaw, nor is the report a warranty against any problems developing after the date of the property report. Refer to NZS 4306:2005 for full details.
	estation in the set of the property report in the tree toos. Loss for full defails
	© 2005 Standards New Zealand. Pads of 40 forms can be ordered from: www.standards.co.nz

	Orientation of living spaces	Inspected Y N N/A		Ceilings	Inspected Y N N/A
SITE	Site exposure, contour & vegetation Retaining walls Paths, steps, handrails & driveways Fencing Surface water control			Walls Timber floors Concrete floors Doors & frames Electrical – operation of switches, etc. Heating systems	
SUBFLOOR	Location of access point Accessibility Foundation type & condition Foundation walls Ground condition Ground vapour barrier Drainage Ventilation adequacy Pile type, instability & condition Pile to bearer connections Obvious structural alteration Ground clearance of timber framing Floor type (timber or suspended concret Timber fraving & bracing Insulation type, approximate thickness, coverage & condition Plumbing – material types, leakage & support Electrical – wiring type & support Insect and pest infestation Rotting timbers Debris	coqoq q qëqooqqqqqqq qqoqo o coccoccoccoc qqoqo o cocqqoccqocco	INTERIOR	Heating systems Kitchen – Bench top Cabinetry Sink Tiles Air extraction system Bathroom, WC, ensuite – Floor Cistern, pan & bidet Tiles Bath Shower Vanity/washbasin Ventilation Special features Laundry – Location Floor Tubs/cabine Tiles Ventilation Storage Stairs Exterior windows & doors	n se se su
EXTERIOR	Construction type Cladding Chimneys Exterior stairs Balconies, verandahs, patios, etc.			Fire warning & control systems Heating systems Central vacuum systems Ventilation systems Security system	) Doooc Doooc
ROOF	Roof material Roof condition Roof water collection Downpipes Eaves, fascia & soffits	99999 10000 10000	SERVICES	Electricity services Gas services Water services Hot water services Foul water disposal Grey water recycling system	1000000
ROOF SPACE	Accessibility Roof cladding Thermal insulation type, clearances, approximate thickness & coverage Sarking Party walls, fire proofing Roof underlay & support			Rainwater collection systems Solar heating Aerials & antennae Shading systems Telecommunications Lifts	inden of
	Roof frame construction & connections Ceiling construction Obvious structural alteration Insect and pest infestation Rotting timbers Discharges into roof space Plumbing – material types, leakage &	i active i	LARY SPACES	Exterior claddings Floors Roofs Subfloor	
	support Electrical – wiring type & support Tile fixings		ANCILLARY		

# **TERMS & CONDITIONS**

#### Scope of the report:

1. P&S Construction shall, subject to the terms herein, undertake the inspection of the Premises in accordance with NZS and prepare a report in accordance with NZS.4306:2005

2. P&S Construction shall consider Weather Tightness of the Premises regardless of age but will not evaluate or report in accordance with appendix A pf NZS or E2/AS1 of the building code, matrix and evaluation as this would be subject to a specialist report.

#### Inspection:

3. The Client will ensure that P&S Construction has lawful and unimpeded and reasonable access to the Premises including, but not limited to, the roof cavities, foundations and spaces and that all such areas are clear for an inspection to be carried out.

4. The Report prepared following visual inspection shall:

(a) indicate any areas of the Premises which were inaccessible or not inspected and the reason why.

(b) identify any significant fault or defect.

(c) suggest wither any significant fault or defect should be referred for a specialist report or for remedial repairs.

5. The inspection is limited to a visual inspection only of the Premises which P&S Construction has reasonable access to and which is in the clear and unobstructed line of site. The inspection does not include any areas of the Premises which cannot be visually inspected due to concealment or obstructions. P&S Construction shall not dismantle equipment or undertake any intrusive or destructive inspection, moving of furniture, appliances, stored items or excavation.

6. The report is not intended to be a warranty or guarantee of the present or future Weather Tightness, adequacy or suitability of the Premises.

#### Limitation

7. The inspection is subject to the limitations set out herein and is not an exhaustive or technical inspection of each and every component of the building on the Premises or every possible defect.

8. The inspection and report excludes;

(a) air conditioning system, dishwashers, stoves, hobbs, heating systems, insulation or heating and cooling equipment, aerials, intercoms, security systems, fire detection systems or heat sensors;

(b) plumbing, gas piping/fitting, drainage and electric systems at the Premises;

(c) the condition of playground equipment;

(d) swimming pools or spas;

(e) the existence or presence of formaldehyde, lead paint, asbestos, toxic or flammable materials, pest infestations, borer, termites, dry rot and health or environmental hazards.

(f) faults which occur intermittently (whether due to absence of use, occupation, concealment or weather);

(g) Resource Management matters or building code conformity.

9. The report is to be used by the Client only as guidance for evaluation of the condition of the Premises and is not intended as an all-encompassing report dealing with the Premises from every aspect.

10. Apart from significant fault or defect the report is limited to items which are not acceptable for their age, condition or type of material.

11. Any suggestion or recommendations contained in the report are suggestions and recommendations only and it is the responsibility of the Client and the person performing the remedial work to ensure the most appropriate remedy is carried out in conjunction with any further discoveries, warranties and any necessary local authority consents are obtained prior to proceeding with remedial work.

12. The Report is valid only for a period of 30 days after the date of the Report after which time the Premises will require re-inspection to determine any changed circumstances which may affect the Report.

13. The inspection and Report should not be construed as a code compliance or an inspection of any legal or territorial authority standards, codes, regulations, or by-laws as they pertain to or affect the Premises. The inspection and Report does include compliance with the NZ building code.

14. The Report is not a structural or land stability survey and does not cover accuracy of fence lines, boundary lines or survey pegs.

15. Any opinions of P&S Construction regarding adequacy, capacity of expected life of components are general statements based on information about similar components and occasional variations are to be expected.

#### Liability

16. The Report is prepared and provided for the confidential use of the Client and their professional advisors. The report may not be copied, reproduced, passed on or sold on in whole or in part or in any form whatsoever unless specifically authorized in writing by P&S Construction. The Report may not be used or relied upon by any person other than the Client unless specifically authorized in writing by P&S Construction. P&S Construction is not liable for any reliance placed on the Report or any loss suffered by any person other than the Client.

17. The liability of P&S Construction is limited to the cost of the Report. P&S Construction shall not be liable for any loss as a result of any act, error or omission of P&S Construction or the Client. The Client hereby indemnifies P&S Construction in respect of any claims concerning any such loss.

#### Terms of trade

18. In consideration of P&S Construction providing the Client with the Report, the Client agrees to the following terms of trade:

(a) Payment is due 7 days after receipt of invoice;

(b) Accounts not paid by the due date shall be charged interest at 2% of the total amount owing per month the account is overdue, together with all debt collection costs.

#### Interpretation

"Client" "NZS"	means the party defined as Client in the report. means the New Zealand Property inspection Standards NZS			
"Premises"	4306:2005. means the property inspected.			
"reasonable access"	means access that is safe and unobstructed and has a minimum clearance of 400-450mm opening access door that can be safely accessed from a 3.6 metre ladder in the ceiling space and 500x 400mm access and crawl space of 500mm vertical clearance for the sub-floor area. If minimum clearance is not available, the area should be within the inspector's unobstructed line of vision.			
"Report" "Weather Tightness"	means this written Report. means the weather tightness as measured in accordance with Appendix A of the NZS or E2/AS1 of the Building Code			
	Appendix A of the NZS or E2/AS1 of the Building Code.			